HISTORIC PROPERTY INVENTORY FORM


INDENTIFICATION SECTION

Field Site No. Site Name Historic Common Field Recorder Owner's Name Address City/State/Zip Code	117-N OAHP No. Ventilation Filter Building Kristine M. Bowen, Evaluator: Darby Stapp U.S. Department of Energy, Richland Operatio P.O. Box 550 Richland, WA 99352	LOCATION SECTION Address City/Town/County/Zip Code Twp. 14N Range 26E Tax No./Parcel No.	111 21st Avenu Olympia, Washi 100-N Reactor Ar Ric Section 28	
Status X Survey/Inventory National Register State Register Determined Eligible Determined Not Eligible Other (HABS, HAER, N Local Designation		Photography Photography Neg. No. (Roll No. & Frame No.) View of West Side Date 1994	Quadrangle or map name UTM References Zone Plat/Block/Lot Supplemental Map(s)	11 Ea
Classification Distric Status Contributing District/Thematic Nomina	District X NR SR Non-Contributing Hanford Site Mar	X Building Structure Object INV hhattan Project and Cold War Era Historic District		
Description Section Materials & Features/Strue Building Type Plan Structural System No. of Stories	ctural Types Industrial Rectangular Reinforced Concrete 1	Roof Type X Gable Hip Flat Pyramidal Monitor Other (specify) Gambrel Shed		
Cladding (exterior Wall Stands Log Horizontal Wood Siding Rustic/Drop Clapboard Wood Shingle Board and Batten Vertical Board		Roof Material Wood Shingle Wood Shake Composition Slate Tar/Built-up Tile		
Asbestos/Asphalt Brick Stone Stucco Terra Cotta X Concrete/Concrete Blo Vinyl/Aluminum Siding Metal (specify) Other (specify)	ck	X Metal (specify) Other (specify) Not visible Foundation Log Concrete Post & Pier Block Stone X Poured Brick Other (specify) Not visible	High Styles/Forms (Check on Greek Revival Gothic Revival Italianate Second Empire Romanesque Revival Stick Style Queen Anne Shingle Style	a or more of the f
Integrity Changes to plan Changes to windows Changes to original cladding Changes to interior Other (specify)	(Include detailed description in Description of Physical Appearance) Intact X X	Slight Moderate Extensive	Colonial Revival Beaux Arts/Neoclassica Chicago/Commercial St American Foursquare Mission Revival Vernacular House Types Gable Front Gable Front and Wing Side Gable	

State of Washington, Department of Community Development Office of Archaeology and Historic Preservation

11 21st Avenue Southwest, Post Office Box 48343 Dlympia, Washington 98504-8343 (206)753-4011

	Richland, W				
Section	28 I/4 Section		NW	1/4 1/4 Sec	SE
				Acreage	
	Coyote Rapid	s 7.5 min.	series	_	
11	Easting	303974		Northing	5172485



Pyramidal/Hipped Other (specify)

NARRATIVE SECTION

Study Unit Themes	(check one or more of the fo	ollowing)						
Agriculture Architecture/Landsca Arts Commerce Communications	ape Architecture		Conservation Education Entertainment/Recreation Ethnic Heritage (specify) Health/Medicine			Politics/Government/La Religion Science & Engineering Social Movements/Org Transportation		
Community Planning/Development			Manufacturing/Industry Military		Other (specify) Study Unit Sub-Them	Manahattan Project & Cold War E	Era	
Statement of Significance	3					Cold War/Nuclear Fuel Waste Management (A		
· ·	1964 surveyor, this property appears to n surveyor, this property is located in	neet the criteria of th	•	General Electric Places.				

The 117-N Ventilation Filter Building was constructed in 1964 and served an essential function in the 105-N Ventilation System, designed to prevent the spread of radioactive contamination. 105-N had five ventilation zones, also known as confinement zones, each served by supply and exhaust fan units, and plenums connected to duct work containing dampers and supply grilles. Air exhausted from Zone 1 (primary radiation area) and Zone II (secondary radiation area) was routed through a high-efficiency particulate air filter system located in the 117-N Filter Building and then discharged to the atmosphere from the 116-N Ventilation Stack. Air from Zone III (normal access areas; metal preparation storage basin, and transfer area), which was normally contamination free, was routed through the 117-N Building but did not pass through any filters; if airborne contamination was detected in a Zone III area, roof exhausters would be shut down and Zone III exhaust air would be routed through the Zone II Exhaust System. Zone IV (unlimited access area) and Zone V (warranted access area) were exhausted directly to the atmosphere.

The 117-N Building housed banks of high-efficiency particulate air filters and charcoal filters, which removed moisture, particulates, and airborne contamination and radionuclides from the 105-N exhaust gases. The Zone I filter structure was composed of two 50% capacity parallel cells (Cells A and B). Filter Cell C provided 100% capacity to the Zone II exhaust system. The standby or emergency cell (Cell D) was capable of 100% Zone II capacity filtration or 50% capacity filtration of Zone I. The first stage of the filter cell was designed as a moisture separator, which prolonged the effectiveness of the second-stage filter. The aluminum mesh moisture separator removed entrained moisture from the exhaust air that might be released during a confinement incident. First-stage filter banks were installed in Cells A, B, and D. The second-stage filter bank consisted of high-efficiency, fire-retardant material designed for continuous operation at a maximum temperature of 200° F and a relative humidity of 100%. The minimum filtration efficiency of the second-stage filter bank was 99.9% for particulate containment. The third-stage filter bank had similar construction features of the second filter bank. The filter media contained activated carbon capable of removing at least 99.9% of all particulate matter and a minimum of 95% of elemental halogen gases that reached the cell.

This property is not associated with an important person (Criterion B), does not possess any distinctive architectural features or methods of construction (Criterion C), and does not qualify under Criterion D as the principal source of important information. However, the 117-N Building qualifies under Criterion A due to its association with the Cold War production of plutonium at N Reactor, and its contribution to Reactor Operations, specifically the Reactor Ventilation System. Therefore, it is the conclusion of the U.S. Department of Energy that the 117-N Building is eligible under Criterion A for inclusion on the National Register of Historic Places as a contributing property within the Hanford Site Manhattan Project and Cold War Era Historic District.

Description of Physical Appearance

The 117-N Building is a rectangular, one-story, reinforced concrete building with a flat galvanized sheet metal roof and poured concrete foundation. A concrete stairway provides access over the earthen and concrete berm surrounding the building. A tunnel was built that leads from the 117-N Building to a second building similar to the 117-N Building, but it was buried over and never used. This building measures approximately 79 ft by 56 ft (24 m by 17 m); 4.424 ft² (408 m²) and has undergone no significant changes.

The N Reactor UTM coordinates are as follows: Northeast corner - 303974E, 5172485N; southeast corner - 303974E, 5171639N; southwest corner - 303069E, 5171639N; northwest corner - 303069E, 5172485N.

Major Bibliographic References

Westinghouse Hanford Company. 1988. N Reactor Updated Safety Analysis Report. WHC-SP-0297, Volume 6, Section 11.3.2.

UNC Nuclear Industries. 1979. N Reactor Plant Manual. UNI-M-94, May 2, 1979.

Architectural & Structural Plans Filter Building, Drawing No. H-1-28401, 1970.